



APPROACH GRADE TABLE								
TRAFFIC TYPE	GRADE PA	RAMETER	MAX. CHANGE IN GRADE	I INITIATIAL CIAL				
TRAFFIC TIPE	G1 (RANGE)	G2 (MAX.)	C (* e)	LENGTH L1				
HIGH VOLUME (COMMERCIAL, INDUSTRIAL)	-2% TO -3%	(+/-) 5%	(+/-) 3%	40'				
LOW VOLUME (COMMERCIAL, INDUSTRIAL)	-2% TO -5%	(+/-) 8%	(+/-) 6%	40'				
SINGLE RESIDENTIAL, FARMYARD, FIELD	-2% TO -8%	(+/-) 15% * g	VEHICLE CLEARANCE	10'				
MULTIPLE RESIDENTIAL	-2% TO -8%	(+/-) 15% * g	(+/-) 6%	20'				
PUBLIC ROAD	-2%	* f	(+/-) 2/	20'				

DEVICIONS

	(* a) STANDARD APPROACH WIDTH TABLE								
	POSTED SPEED (mph)	≤3	5	>35					
	MIN./MAX. WIDTH	MIN.	MAX.	MIN.	MAX.				
APPR. TYPE	MULTIPLE RESIDENTIAL	28'	40'	28'	40'				
	SINGLE RESIDENTIAL, FARMYARD, FIELD	12'	40'	20'	40'				
	COMMERCIAL (ONE-WAY)	15'	30'	20'	30'				
	COMMERCIAL (TWO-WAY)	25'	40'	25'	40'				
	PUBLIC ROAD	28'	N/A	28'	N/A				





NOTES

(SEE NOTE NO. 10)

1. RURAL PRIVATE, COMMERCIAL, AND PUBLIC APPROACHES SHALL BE PAVED TO THE RIGHT-OF-WAY LINE OR TO THE BACK OF THE SHOULDER CURVE (APPROACH RADIUS). FARMYARD AND FIELD APPROACHES THAT ARE OCCASIONALLY USED MAY BE PAVED A MINIMUM OF 5' FROM THE SHOULDER LINE. APPROACHES ON EXISTING

2. REFER TO THE ITD ADMINISTRATIVE POLICY (A-12-01) FOR ADDITIONAL INFOR-MATION ON LOCATION OF APPROACHES.

3. WITHIN THE CLEARZONE THE SIDE SLOPES OF APPROACHES SHALL BE A MINIMUM OF 6:1 OF SECONDARY HIGHWAYS AND A MINIMUM OF 10:1 ON PRIMARY HIGHWAYS.

4. WHEN THE "MAXIMUM CHANGE IN GRADE" (APPROACH GRADE TABLE) "C" IS EXCEEDED, A MINIMUM 10' VERTICAL CURVE SHALL BE USED IN THE APPROACH

5. THE % GRADE OF "G2" SHALL BE A MAXIMUM OF 7% FOR FLAT TERRAIN, 11% FOR ROLLING TERRAIN, OR 15% FOR MOUNTAINOUS.

 $6.\ \mbox{APPROACH}$ GRADES EXCEEDING 10% ARE NOT RECOMMENDED BECAUSE EMERGENCY VEHICLES MAY BE IMPEDED.

7. THE BALLAST REQUIREMENTS OF RURAL APPROACHES SHALL BE AS SHOWN ON

8. WHEN A MAILBOX TURNOUT IS INSTALLED WITH A RURAL APPROACH, STD. DWG. H-4-B IS REQUIRED.

9. ALL RURAL PRIVATE AND COMMERCIAL APPROACHES SHALL BE DESIGNED AND CONSTRUCTED IN A MANNER THAT THE APPROACH DRAINAGE IS INDEPENDENT AND DOES NOT CONTRIBUTE TO EXISTING HIGHWAY DRAINAGE. ALL RURAL PUBLIC APPROACHES SHALL BE DESIGNED AND CONSTRUCTED TO ADDRESS BOTH THE MAIN HIGHWAY AND APPROACH DRAINAGE.

10. THE APPROACH SKEW ANGLE IS THE DEFLECTION ANGLE BETWEEN A LINE PERPENDICULAR TO THE HIGHWAY CENTERLINE AND THE APPROACH CENTERLINE. 11. RURAL PRIVATE AND COMMERCIAL APPROACHES ARE REFERENCED LEFT OR RIGHT OF THE HIGHWAY CENTERLINE STATION TO THE CENTER OF THE APPROACH OPENING WHICH IS AT THE EDGE OF PAVEMENT OR BACK OF CURB. A PUBLIC APPROACH STATION OCCURS WHERE THE PUBLIC APPROACH CENTERLINE INTERSECTS THE HIGHWAY CENTERLINE.

12. NOT TO SCALE.

STANDARD DRAWING

RURAL APPROACHES PRIVATE, COMMERCIAL, & PUBLIC) English STANDARD DRWG. NO H-4-A

LE ATOTONO										SCALES SHOWN	IDAHO IDAHO	
	NO.	DATE	BY	NO.	DATE	BY	NO.	DATE	BY	ARE FOR 11" X 17"	XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	
	1	1-00	MSM	6	12-05	MSM				PRINTS ONLY	TRANSPORTATION ASSISTANT CHIEF ENGINEER (DEVELOPMENT)	
	2	1-02	MSM	7	6-07	MSM				CADD FILE NAME	I DEPARIMENT SEE IN THE TENER OF THE PROPERTY	
[3	7-02	MSM							h4a_0607.std	DEPARIMENT The C. Inthus	(P
L	4	10-02	MSM							DRWG. ORIG. DATE:	0.000	••
1	5	8-04	MSM							SEPTEMBER, 1993	BOISE IDAHO CHIEF ENGINEER	

SHEET 1 OF